

- 1. ALL DIMENSIONS ARE IN MILLIMETRES AND LEVELS IN METRES UNLESS NOTED OTHERWISE.
- 2. USE FIGURED DIMENSIONS ONLY. DO NOT SCALE.
- 3. DRAWINGS TO BE READ IN CONJUNCTION WITH ALL RELEVANT PROJECT BRIEFS, SPECIFICATIONS & PRICING DOCUMENTS.
- 4. CONTRACTOR TO ALLOW FOR SITE SETUP, STORAGE COMPOUND & ALL ANCILLARY MEASURES NECESSARY TO CARRY OUT THE WORKS
- 5. CONTRACTOR TO UNDERTAKE ROLE OF PROJECT SUPERVISOR CONSTRUCTION STAGE (PSCS).
- CONTRACTOR TO MAINTAIN VEHICULAR THROUGH ACCESS ALONG ROAD AT ALL TIMES FOR THE DURATION OF THE
- 7. CONTRACTOR TO ALLOW FOR ALL TRAFFIC MANAGEMENT ARRANGEMENTS AND OBTAINING ROAD OPENING LICENSES AS NECESSARY.
- 8. CONTRACTOR TO IDENTIFY & PROTECT ALL EXISTING
- SERVICES WITHIN THE WORKS AREA AT OUTSET OF WORKS. EXISTING DRAINAGE INFRASTRUCTURE HAS BEEN SHOWN
 BASED ON AVAILABLE TOPOGRAPHICAL & OTHER SURVEY
- ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH CURRENT BUILDING REGULATIONS.
 TACTILE PAVING TO BE INSTALLED IN ACCORDANCE WITH
- GUIDANCE ON THE USE OF TACTILE PAVING SURFACES DOCUMENT &TII STANDARD DETAIL CC-SCD-05536.
- 12. KERBS, FOOTWAYS AND PAVED AREAS TO BE IN ACCORDANCE WITH TII PUBLICATIONS FOOTWAY DESIGN & VOLUME 1 SPECIFICATION FOR ROAD WORKS SERIES 1100 KERBS, FOOTWAYS AND PAVED AREAS.
- 13. FOOTPATH REINSTATMENTS OR FOOTPATH EXTENSIONS MUST MATCH EXISTING SURFACES.
- 14. ALL SIGNAGE AND ROAD MARKINGS TO BE IN ACCORDANCE WITH THE TRAFFIC SIGNS MANUAL.

 15. REINSTATE ROAD MARKINGS TO ALSO BE IN ACCORDANCE WITH IS EN 1436 EUROPEAN STANDARD FOR ROAD
- 16. REMOVE AND RELOCATE STOP/ YIELD ROAD MARKINGS WHERE NECESSARY.

 17. REMOVE AND RELOCATE LINE MARKINGS WHERE
- 18. ALL NEW / REPLACEMENT MANHOLE COVERS & GULLEY GRATES TO LOADING CLASS D400.

 19. CONTRACTOR TO ALLOW FOR CONNECTION OF ALL
- EXISTING & NEW ROAD GULLEYS TO EXISTING SURFACE WATER DRAINAGE PIPEWORK.
 20. CONTRACTOR TO ALLOW FOR ALTERATIONS TO EXISTING
- BOUNDARY BOXES, WATER METERS, HYDRANTS, SLUICE VALVES & SCOUR VALVES WITHIN WORKS AREA.
- 21. JOINTS TO BE PROVIDED IN CONCRETE FOOTPATHS TO ACCOMMODATE HORIZONTAL MOVEMENT DUE TO CHANGES IN TEMPERATURE & MOISTURE CONTENT.
- 22. ON COMPLETION, CONTRACTOR TO ALLOW FOR MAKING GOOD TO ALL AREAS AFFECTED BY THE WORKS.

Revision	Description of Changes made	Ву	Date



E: rdo@clarecoco.ie W: www.clarec

Connecting & Co- Creating Ennis

Uncontrolled Crossing- Circular Road Ard Na Gaoithe

Status:	TENDER	Drawing No.:	Rev:
Designed by:	JB	D 0000 70 00 00 050	
Drawn by:	JB	R.2022.70.09.23.053	-
Checked by:	Cmc		
Approved by:	Cmc	Location:	
Scale:	1:200 @ A3		
Date:	21/09/2022		J

