

NOTES

- ALL DIMENSIONS ARE IN MILLIMETRES AND LEVELS IN METRES UNLESS NOTED OTHERWISE.
- 2. USE FIGURED DIMENSIONS ONLY. DO NOT SCALE.
- DRAWINGS TO BE READ IN CONJUNCTION WITH ALL RELEVANT PROJECT BRIEFS, SPECIFICATIONS & PRICING DOCUMENTS.
- 4. CONTRACTOR TO ALLOW FOR SITE SETUP, STORAGE COMPOUND & ALL ANCILLARY MEASURES NECESSARY TO CARRY OUT THE WORKS.
- CONTRACTOR TO UNDERTAKE ROLE OF PROJECT SUPERVISOR CONSTRUCTION STAGE (PSCS).
- CONTRACTOR TO MAINTAIN VEHICULAR THROUGH ACCESS ALONG ROAD AT ALL TIMES FOR THE DURATION OF THE WORKS.
- CONTRACTOR TO ALLOW FOR ALL TRAFFIC MANAGEMENT ARRANGEMENTS AND OBTAINING ROAD OPENING LICENSES AS NECESSARY.
- CONTRACTOR TO IDENTIFY & PROTECT ALL EXISTING
 SERVICES WITHIN THE WORKS AREA AT OUTSET OF WORKS.
- EXISTING DRAINAGE INFRASTRUCTURE HAS BEEN SHOWN
 BASED ON AVAILABLE TOPOGRAPHICAL & OTHER SURVEY
 INFORMATION.
- 10. ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH
- CURRENT BUILDING REGULATIONS.

 11. TACTILE PAVING TO BE INSTALLED IN ACCORDANCE WITH GUIDANCE ON THE USE OF TACTILE PAVING SURFACES DOCUMENT &TII STANDARD DETAIL CC-SCD-05536.
- 12. KERBS, FOOTWAYS AND PAVED AREAS TO BE IN ACCORDANCE WITH TII PUBLICATIONS FOOTWAY DESIGN & VOLUME 1 SPECIFICATION FOR ROAD WORKS SERIES 1100 KERBS, FOOTWAYS AND PAVED AREAS.
- 13. FOOTPATH REINSTATMENTS OR FOOTPATH EXTENSIONS MUST MATCH EXISTING SURFACES.
- 14. ALL SIGNAGE AND ROAD MARKINGS TO BE IN ACCORDANCE WITH THE TRAFFIC SIGNS MANUAL.
- REINSTATE ROAD MARKINGS TO ALSO BE IN ACCORDANCE WITH IS EN 1436 EUROPEAN STANDARD FOR ROAD MARKINGS.
- 16. REMOVE AND RELOCATE STOP/ YIELD ROAD MARKINGS WHERE NECESSARY.
- 17. REMOVE AND RELOCATE LINE MARKINGS WHERE
- 18. ALL NEW / REPLACEMENT MANHOLE COVERS & GULLEY GRATES TO LOADING CLASS D400.
 19. CONTRACTOR TO ALLOW FOR CONNECTION OF ALL
- CONTRACTOR TO ALLOW FOR CONNECTION OF ALL EXISTING & NEW ROAD GULLEYS TO EXISTING SURFACE WATER DRAINAGE PIPEWORK.
 CONTRACTOR TO ALLOW FOR ALTERATIONS TO EXISTING
 - BOUNDARY BOXES, WATER METERS, HYDRANTS, SLUICE VALVES & SCOUR VALVES WITHIN WORKS AREA.
- 21. JOINTS TO BE PROVIDED IN CONCRETE FOOTPATHS TO ACCOMMODATE HORIZONTAL MOVEMENT DUE TO CHANGES IN TEMPERATURE & MOISTURE CONTENT.
- 22. ON COMPLETION, CONTRACTOR TO ALLOW FOR MAKING GOOD TO ALL AREAS AFFECTED BY THE WORKS.

Revision	Description of Changes made	Ву	Date



ct Title:

Connecting & Co- Creating Ennis

Uncontrolled Crossings - Circular Road at entrance to Hermitage

Status:	TENDER	Drawing No.:	Rev:
Designed by:	JB		
Drawn by:	JB	R.2022.70.09.23.050	-
Checked by:	Cmc		
Approved by:	Cmc	Location:	•
Scale:	1:200 @ A3		
Date:	20/09/2022		

O THIS BRAYING AND ANY DESIGN RESERVE THE COPYRIGHT OF CLARE COUNTY COUNCE, AND ANY NOT BE OFFICE REPORTAGED OR OTHER CONTROL OF THE CLARE COUNTY COUNCE. AND DESIGNED THE OFFICE AND COUNTY COUNCE. AND COUNTY COUNCE. AND COUNTY COUNTY