

NOTES:

- 1. ALL DIMENSIONS AND LEVELS ARE IN METRES UNLESS NOTED OTHERWISE.
- 2. USE FIGURED DIMENSIONS ONLY. DO NOT SCALE.
- 3. DRAWINGS TO BE READ IN CONJUNCTION WITH ALL RELEVANT PROJECT BRIEFS, SPECIFICATIONS, PRICING DOCUMENTS & 'SAFE ROUTES TO SCHOOL' GUIDANCE.
- 4. CONTRACTOR TO ALLOW FOR SITE SETUP, STORAGE COMPOUND & ALL ANCILLARY MEASURES NECESSARY TO CARRY OUT THE WORKS.
- 5. CONTRACTOR TO UNDERTAKE ROLE OF PROJECT SUPERVISOR
- CONSTRUCTION STAGE (PSCS).


REGULATIONS.

- 6. CONTRACTOR TO MAINTAIN VEHICULAR THROUGH ACCESS ALONG ROAD AT ALL TIMES FOR THE DURATION OF THE WORKS.
- 6. CONTRACTOR TO MAINTAIN PEDESTRIAN ACCESS ALONG ROADWAY FOR RESIDENTS AND SCHOOL PATRONS AT ALL TIMES FOR THE DURATION OF
- 7. TEMPORARY DELINEATED WALKWAYS TO BE INSTALLED BY CONTRACTOR THROUGHOUT WORKS AREA AS NECESSARY TO ENSURE PEDESTRIAN ACCESS AND SAFETY FOR DURATION OF WORKS.
- 8. CONTRACTOR TO ALLOW FOR ALL TRAFFIC MANAGEMENT PLANS,
- ARRANGEMENTS AND OBTAINING ROAD OPENING LICENSES AS NECESSARY. 9. CONTRACTOR TO IDENTIFY & PROTECT ALL EXISTING SERVICES WITHIN THE
- WORKS AREA AT OUTSET OF WORKS. 10. EXISTING DRAINAGE INFRASTRUCTURE HAS BEEN SHOWN BASED ON
- AVAILABLE TOPOGRAPHICAL & OTHER SURVEY INFORMATION. 11. ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH CURRENT BUILDING
- 12. TACTILE PAVING TO BE INSTALLED IN ACCORDANCE WITH GUIDANCE ON THE USE OF TACTILE PAVING SURFACES DOCUMENT
- 13. KERBS, FOOTWAYS AND PAVED AREAS TO BE IN ACCORDANCE WITH TII PUBLICATIONS FOOTWAY DESIGN & VOLUME 1 SPECIFICATION FOR ROAD WORKS SERIES 1100 KERBS, FOOTWAYS AND PAVED AREAS.
- 14. ALL SIGNAGE AND ROAD MARKINGS TO BE IN ACCORDANCE WITH THE TRAFFIC SIGNS MANUAL.
- 15. ROAD MARKINGS TO ALSO BE IN ACCORDANCE WITH IS EN 1436 EUROPEAN STANDARD FOR ROAD MARKINGS.
- 16. PRECAST CONCRETE GULLEYS AND COVER SLABS SHALL BE TO IS EN 1917
- 17. ALL NEW / REPLACEMENT MANHOLE COVERS & GULLEY GRATES TO LOADING
- CLASS D400. 18. CONTRACTOR TO ALLOW FOR CONNECTION OF ALL EXISTING & NEW ROAD
- GULLEYS TO EXISTING SURFACE WATER DRAINAGE PIPEWORK
- 19. CONTRACTOR TO ALLOW FOR ALTERATIONS TO EXISTING BOUNDARY BOXES, WATER METERS, HYDRANTS, SLUICE VALVES & SCOUR VALVES WITHIN WORKS AREA.
- TO BE INSTALLED IN ACCORDANCE WITH ELECTRICAL SPECIALIST SPECIFICATION. 21. CONTRACTOR TO INSTALL POTS IN CONCRETE SURROUND TO SPECIALIST

20. CONTRACTOR TO ENSURE DUCTING FOR NEW PUBLIC LIGHTING COLUMNS

- SPECIFICATION AT ALL LOCATIONS DENOTED ON DRAWING FOR PUBLIC LIGHTING COLUMNS.
- 22. CONTRACTOR TO FACILITATE SPECIALIST IN THE INSTALLATION OF PUBLIC LIGHTING COLUMNS & ASSOCIATED ELECTRICAL WIRING WORKS.
- 23. SURFACING OF FOOTPATHS TO BE CARRIED OUT AFTER COMPLETION OF
- ELECTRICAL WORKS. 24. JOINTS TO BE PROVIDED IN CONCRETE FOOTPATHS TO ACCOMMODATE HORIZONTAL MOVEMENT DUE TO CHANGES IN TEMPERATURE & MOISTURE
- 25. ON COMPLETION, CONTRACTOR TO ALLOW FOR MAKING GOOD TO ALL AREAS AFFECTED BY THE WORKS.

Revision	Description of Changes Made	Ву	Date
			,



CLARE COUNTY COUNCIL Road Design Office, Áras Contae an Chláir, New Road, Ennis, Co. Clare T: 065 6821616 F: 065 68 21915 E: rdo@clarecoco.ie W: www.clarecoco.ie

Project Title:

SPECIFIC IMPROVEMENT SCHEME -OGONNELLOE

Drawing Title: Proposed Site Layout

Status:	Draft	Drawing No.:	Rev:			
Designed by:	KOC	R.53.01.02.03-500				
Drawn by:	C.E.					
Checked by:	KOC					
Approved by:	AOS	Location:				
Scale:	1: 200 @ A1	W:\53.0 Specific Improvement Schemes (SIG)\53.01 Ogonnelloe\Phase 2\53.01.02.03 Design				
Date:	10.09.2025					