

Legend

Existing kerb


Proposed new kerbing

Existing footpath

Proposed new footpath

- NOTES:
- ALL DIMENSIONS AND LEVELS ARE IN METRES UNLESS NOTED OTHERWISE.
 - USE FIGURED DIMENSIONS ONLY. DO NOT SCALE.
 - DRAWINGS TO BE READ IN CONJUNCTION WITH ALL RELEVANT PROJECT BRIEFS, SPECIFICATIONS, PRICING DOCUMENTS & 'SAFE ROUTES TO SCHOOL' GUIDANCE.
 - CONTRACTOR TO ALLOW FOR SITE SETUP, STORAGE COMPOUND & ALL ANCILLARY MEASURES NECESSARY TO CARRY OUT THE WORKS.
 - CONTRACTOR TO UNDERTAKE ROLE OF PROJECT SUPERVISOR CONSTRUCTION STAGE (PSCS).
 - CONTRACTOR TO MAINTAIN VEHICULAR THROUGH ACCESS ALONG ROAD AT ALL TIMES FOR THE DURATION OF THE WORKS.
 - CONTRACTOR TO MAINTAIN PEDESTRIAN ACCESS ALONG ROADWAY FOR RESIDENTS AND SCHOOL PATRONS AT ALL TIMES FOR THE DURATION OF THE WORKS.
 - TEMPORARY DELINEATED WALKWAYS TO BE INSTALLED BY CONTRACTOR THROUGHOUT WORKS AREA AS NECESSARY TO ENSURE PEDESTRIAN ACCESS AND SAFETY FOR DURATION OF WORKS.
 - CONTRACTOR TO ALLOW FOR ALL TRAFFIC MANAGEMENT PLANS, ARRANGEMENTS AND OBTAINING ROAD OPENING LICENSES AS NECESSARY.
 - CONTRACTOR TO IDENTIFY & PROTECT ALL EXISTING SERVICES WITHIN THE WORKS AREA AT OUTSET OF WORKS.
 - EXISTING DRAINAGE INFRASTRUCTURE HAS BEEN SHOWN BASED ON AVAILABLE TOPOGRAPHICAL & OTHER SURVEY INFORMATION.
 - ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH CURRENT BUILDING REGULATIONS.
 - TACTILE PAVING TO BE INSTALLED IN ACCORDANCE WITH GUIDANCE ON THE USE OF TACTILE PAVING SURFACES DOCUMENT.
 - KERBS, FOOTWAYS AND PAVED AREAS TO BE IN ACCORDANCE WITH TII PUBLICATIONS FOOTWAY DESIGN & VOLUME 1 SPECIFICATION FOR ROAD WORKS SERIES 1100 KERBS, FOOTWAYS AND PAVED AREAS.
 - ALL SIGNAGE AND ROAD MARKINGS TO BE IN ACCORDANCE WITH THE TRAFFIC SIGNS MANUAL.
 - ROAD MARKINGS TO ALSO BE IN ACCORDANCE WITH IS EN 1436 EUROPEAN STANDARD FOR ROAD MARKINGS.
 - PRECAST CONCRETE GULLIES AND COVER SLABS SHALL BE TO IS EN 1917 OR BS 5911-6.
 - ALL NEW / REPLACEMENT MANHOLE COVERS & GULLEY GRATES TO LOADING CLASS D400.
 - CONTRACTOR TO ALLOW FOR CONNECTION OF ALL EXISTING & NEW ROAD GULLEYS TO EXISTING SURFACE WATER DRAINAGE PIPEWORK.
 - CONTRACTOR TO ALLOW FOR ALTERATIONS TO EXISTING BOUNDARY BOXES, WATER METERS, HYDRANTS, SLUICE VALVES & SCOUR VALVES WITHIN WORKS AREA.
 - CONTRACTOR TO ENSURE DUCTING FOR NEW PUBLIC LIGHTING COLUMNS TO BE INSTALLED IN ACCORDANCE WITH ELECTRICAL SPECIALIST SPECIFICATION.
 - CONTRACTOR TO INSTALL POTS IN CONCRETE SURROUND TO SPECIALIST SPECIFICATION AT ALL LOCATIONS DENOTED ON DRAWING FOR PUBLIC LIGHTING COLUMNS.
 - CONTRACTOR TO FACILITATE SPECIALIST IN THE INSTALLATION OF PUBLIC LIGHTING COLUMNS & ASSOCIATED ELECTRICAL WIRING WORKS.
 - SURFACING OF FOOTPATHS TO BE CARRIED OUT AFTER COMPLETION OF ELECTRICAL WORKS.
 - JOINTS TO BE PROVIDED IN CONCRETE FOOTPATHS TO ACCOMMODATE HORIZONTAL MOVEMENT DUE TO CHANGES IN TEMPERATURE & MOISTURE CONTENT.
 - ON COMPLETION, CONTRACTOR TO ALLOW FOR MAKING GOOD TO ALL AREAS AFFECTED BY THE WORKS.

| Revision | Description of Changes Made | By | Date |
|----------|-----------------------------|----|------|
| | | | |
| | | | |
| | | | |



CLARE COUNTY COUNCIL

Road Design Office, Aras Contae an Chláir, New Road, Ennis, Co. Clare
T: 065 6821616 F: 065 68 21915
E: rdo@clarecoco.ie W: www.clarecoco.ie

Project Title:

SPECIFIC IMPROVEMENT SCHEME
OGONNELLOE

Drawing Title:

Proposed Site Layout

Status:

Designed by: KOC

Drawn by: C.E.

Checked by: KOC

Approved by: AOS

Scale: 1: 200 @ A1

Date: 10.09.2025

Drawing No.:

R.53.01.02.03-700

Rev:

Location:

W:\53.0 Specific Improvement Schemes (SIG)\53.01
Ogonnelloe\Phase 2\53.01.02.03 Design